

आर्यावर्त बैंक

भारत सरकार, उप सरकार एवं बैंक ऑफ इंडिया का संयुक्त उपक्रम
प्रधान कार्यालय: लखनऊ
क्षेत्रीय कार्यालय : चित्रकूट



ARYAVART BANK

(A Joint Undertaking of Govt. of India, U.P. Govt. and Bank of India)

Head Office : Lucknow

Regional Office : Chitrakoot

ROCHIT/A&S/ 2023-24/ 591

दिनांक: 28-08-2023

सेवा में,

महाप्रबंधक महोदय
प्रशा० एवं सेवा० विभाग
आर्यावर्त बैंक,
प्रधान कार्यालय, लखनऊ

महोदय,

शाखा कर्मी में सिविल कार्य हेतु निविदा वेबसाइट पर प्रदर्शित करने के सम्बन्ध में

प्रधानकार्यालय के पत्रांक HO/A&S/PVS/584/2023-24 दिनांक 23.08.2023 द्वारा दी गयी स्वीकृति के आधार पर शाखा कर्मी में सिविल कार्य की निविदा हेतु विज्ञापन की प्रति बैंक की वेबसाइट पर अपलोड करने हेतु प्रेषित है।
उपरोक्त से सम्बंधित विज्ञापन दिनांक 31.08.2023 को दैनिक समाचार पत्र में प्रकाशित कराया जायेगा

संगलन : यथोपरि।

भवदीय

क्षेत्रीय प्रबन्धक

न

आवश्यक सूचना

आर्यावर्त बैंक की शाखा कर्वी के भवन परिसर में मरम्मत के कार्य किये जाने की आवश्यकता है। जिसमे भवन परिसर में प्लास्टर, पुट्टी, पेंट, टाइल्स लगवाना इत्यादि कार्य शामिल हैं। इच्छुक व्यक्ति/संस्था, आर्यावर्त बैंक क्षेत्रीय कार्यालय / शाखा पुरानी बाज़ार (वर्तमान शाखा कर्वी का संचालन केंद्र) से सम्पर्क कर प्रारूप प्राप्त कर सकते हैं तथा अपना प्रस्ताव निर्धारित प्रारूप पर भरकर दिनांक-15.09.2023, सायं 5:00 तक क्षेत्रीय कार्यालय बेड़ीपुलिया अमानपुर / शाखा पुरानी बाज़ार (वर्तमान शाखा कर्वी का संचालन केंद्र) चित्रकूट में बंद लिफाफे में व्यक्तिगत रूप से उपस्थित होकर/रजिस्टर्ड डाक के माध्यम से प्रस्तुत कर सकते हैं।

अधिक जानकारी के लिए आप हमारी वेबसाइट [**www.aryavart-rrb.com**](http://www.aryavart-rrb.com) पर विजिट कर सकते हैं।

Architects Engineers & Valuers

- Government of India Registered Valuer :
- Income Tax Reg No. 262/2003 CAT 1 Immovable Property
- Institute of International Appraisers & Valuers
- Corporate Member of Institution of Engineers (India)
- Chartered Engineer Registration No. AM 082832/C/5
- Approved Architect (A.I.I.A. App.)
- Expert in Water Proofing for Multistoried Residential and Commercial Building
- Soil Testing, Cube Testing and Antitermite Treatment
- Member of Indian Road Congress
- Fellowship Approved
- Institute of International Appraisers and Valuers
- Institute of Valuers (India) Reg. No. IV-9321
- Indian Association of Structural Engineers
- Member of Consulting Engineer Association of India



CORNER'S 'n' EDGES

Prop. **Vivek Singh**

B.E. (CIVIL), M.I.E., (Arch.)
FIV., A.M.I.E., A.M.I.V., M.I.R.C.
CHARTERED ENGINEER

Quotation

- 1> Property / Plot No. : Aryavart Bank Main Branch Karvi
- 2> Name of Institution : Aryavart Bank Karvi Br RO Chitrakoot
- 3> Location : Na
- 4> Purpose : Repair work
- 5> Quotation on : 23.08.2023
- 6> Nature of Work : Work of Iron & Flooring work
- 7> Total Plot Area : N a

Amount	→	Rs.	
---------------	---	------------	--

**VIVEK
SINGH**

Digitally signed
by VIVEK SINGH
Date: 2023.08.24
12:34:33 +05'30'

ABSTRACT SHEET

Aryavart Bank Main Branch Karvi						
Aryavart Bank Karvi Br RO Chitrakoot						
S.No	Particulars of Item	Qty	Unit	Rate	Per	Amount
1	Dismantling cement concrete workor Brick Or granolithic floors including base concrete & stacking of dismantled materials as directed by incharge	257	Sqm		Sqm	
2	Dismantling existing Plaster work including disposal of refuse , Scraping old white or colour wash including disposal materials as directed by incharge	195	SQM		SQM	
3	12mm. thick Plaster in wall in 1 : 3 cement & coarse sand	252	SQM		SQM	
4	12 mm thick Plaster in ceiling in 1:2 cement & coarse sand and repair labour. C/C Wall	158	SQM		SQM	
5	Painting in Wall & Ceiling & vanishing on iron work in small areas two coats of approved superior quality ISI mark as Asian , Berger Etc	553	SQM		SQM	
6	Mild Steel or Iron work in heavy size.	445	Kg		Kg.	
7	Supply & Fixing 4 mm thick glass panes	12	SQM		SQM	

8	Providing & laying Ceramic Glazed Floor Tiles 300x300 mm (thickness to be specified by the manufacturer) of Ist Quality confirming to IS :13755 of NITCO,ORIENT, SOMANY, KAJARIA, or equivalent make in colours .Such As White, Ivory, Grey , Fume, Red, Brown , laid on 20MM thick cement Mortar 1:3 (cement & C/Sand) including the Joints with white cement & matching Pigments etc . Complete .	228	SQM		SQM	
---	--	-----	-----	--	-----	--

<u>Total Amount</u>	➡	Rs.	
----------------------------	---	------------	--

**VIVEK
SINGH**

Digitally signed
by VIVEK SINGH
Date: 2023.08.24
12:35:42 +05'30'

Note:- All Quantities / Measurements are subject to final measurement on site in the presence of Architect/Engineer/ Bank official and are subjected to variation up to 15% to 20%.

TERMS AND CONDITIONS

A

All Materials to be used should of proper thickness (as detailed above) free from defects of warping uneven surface I.S.I. approved

B

Before construction of material at site it should be inspected and approved by an Architect/ authorized by the Bank to ensure use of proper material. Use of non-approved brand of cement , Painting items etc is strictly prohibited and fixing of material before proper inspection should be avoided. Material used without proper inspection may be totally rejected.

C

Rate quoted must be F.O.R. i.e. at branch ; bank will not pay any transportation, packing, loading, and unloading charges.

D

The work if awarded is required to be completed in given time, delay will attract penalty @5.00%for 15 days block or part there of.

E

The clear Tile & Painting work is requiried to be of good quality,

F

The Finishing work will be checked and verified by the architect / chief manager (A & S) / Regional manager or their representative.

G

In case of any clarification / difficulty , you may contact bank's architect or officer A &S Department