



**GRAMIN BANK OF ARYAVART**  
HEAD OFFICE, A – 2/46, GOMTINAGAR, LUCKNOW (U.P.) 226010  
PHONE NO.7388800775/76/88/90, EMAIL ID- [HO.ANS@GBA-RRB.COM](mailto:HO.ANS@GBA-RRB.COM)

HO/A&S/PVS/01/2018-19

Date: 02.04.2018

**Corrigendum**

**Proposed Air Conditioning Work for Gramin Bank of Aryavart At Farrukhabad**

Please refer to our tender notice for Air Conditioning works for Gramin Bank of Aryavart at Farrukhabad,

Following modifications must be observed in the tender notice:

1. The Revised Financial Bid (**copy enclosed**) {Bill of Quantity for Air Conditioning Work for Gramin Bank of Aryavart} must be substituted with the previous one.

The last date for submission is 09.04.2018 (Monday), the technical bids will be opened on 10.04.2018  
Rest all terms and conditions will remain the same.

**P V Sahai**  
(Chief Manager)





Gramin Bank of Aryavart  
A-2/46, Vijay Khand, Gomti Nagar, Lucknow  
PHONE NO.7388800775/76/88/90, EMAIL [ID-ho.ans@gba-rrb.com](mailto:ID-ho.ans@gba-rrb.com)  
(each page of this financial bid must be signed)

**BILL OF QUANTITY FOR AIR-CONDITIONING WORK FOR GRAMIN BANK OF ARYAVART**

**AT REGIONAL OFFICE, FARRUKHABAD**

S.No.	Item	Unit	Qty.	Rate	Amount
1	Supply and Installation of wall mounted split AC 1.0 Ton 3 star .(AC BLUE STAR, DAIKIN, HITACHI VOLTAS MAKE ONLY) - This would include 5 year warranty on the compressor.	No.	1		
	Supply and Installation Of wall mounted split AC 1.5 Ton 3 star .(AC BLUE STAR,DAIKIN,HITACHI VOLTAS,MAKE, ONLY - . This would include 5 year warranty on the compressor.	No	18		
3	Supply and Installation Of wall mounted split AC 2Ton 3 star .(AC BLUE STAR,DAIKIN,HITACHI ,VOLTAS,MAKE, ONLY - .This would include 5 year warranty on the compressor	No	1		
4	Copper Piping Refrigerant along with insulator Piping for Hi Wall . 19 G Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube above 4 RMT length available with spilt AC machine.	Mts	155.00		
5	<b>Frame Work</b> Supply, Fabrication and installation Of MS base Frame for outdoor unit complete with epoxy painting vibration isolation pads, supports, hangers, railing brackets etc. with cage and lockning arrangement.	No	20		
6	Drain Water Piping Constructed out of PVC Hard Pipes, fitting, accessories, bends, elbows, tees, hanger, support, anchors, ISI approved Finolex/Prince Make (32mm)	Mtr	185		
7	Providing & Installation of 5KVA voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Serval,Stambh)	No	1		





8	Providing & Installation of 4KVA voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Servel, Stambh)	No	19		
<b>TOTAL</b>					

Signature of the Tenderer

