



Aryavart Bank

A-2 /46, Vijay Khand, Gomti Nagar, Lucknow

(AN UNDERTAKING OF GOVT OF INDIA, U.P. GOVT. & BANK OF INDIA)
www.aryavart-rrb.com

Ref. No:HO/A&S/PKS/1005/2020-21

Date:08-03-2021

Corrigendum

For

**Supply, Installation, Commissioning, Testing and Maintenance
of Online UPS at Various Branches and offices of the Bank**

Please refer our tender notice ref. no. HO/A&S/PKS/948/2020-21 dated: 11-02-2021 for Supply, Installation, Commissioning, Maintenance and Testing of Online UPS at various branches/offices of our Bank. After the pre bid meeting held on 06-03-2021 Bank has decided to add following conditions in tender document:

S.N.	Page no. & Point no.	Existing Term	Revised term
1.	Page no. 2 Last date and Time for submission of Bids	09-03-2021	15-03-2021 till 5:00 PM
2.	Page no. 2 Date for opening of technical bids	10-03-2021	16-03-2021
3.	Page no. 8 Point no. b	Buyback rates shall not be included for arriving at L1 vendor.	Buyback rates shall not be included for arriving at L1 vendor and buyback should be obtained on the 'as is where is' basis.
4.	Page no. 10 Point no. 22	PEANLTY FOR DELAY IN DELIVERY: Vendor has to deliver goods in 10 days but if the delivery is unduly delayed by more than 05 days after 10 days, a penalty of Rs.100/- per day from the date of purchase order is liable to be levied.	PEANLTY FOR DELAY IN DELIVERY: Vendor has to deliver goods in 6 weeks but if the delivery is unduly delayed after 6 weeks, a penalty of Rs.100/- per day from the date of purchase order is liable to be levied.



5.	Page no. 12 Point no. 23.q	New term	OEM will authorized only one system implementer.
6.	Page no.24 Point no.14.2	The warranty period shall be 48 months for online UPS from date of acceptance of the online UPS Provided that wherever the online UPS could not be installed due to the site not being ready or for any reason attributable solely to the Bank, the warranty shall terminate after 60 months for UPS from the date of Installation. The Supplier shall, in addition, comply with the performance guarantees specified under the Contract. If, for reasons attributable to the Supplier, these guarantees are not attained in whole or in part, the Supplier shall, make such changes, modifications, and/or additions to the Goods or any part thereof as may be necessary in order to attain the contractual guarantees specified in the Contract at its own cost and expense and to carry out further performance tests in accordance with TCC Clause 7.	The warranty period shall be 60 months for online UPS from date of acceptance of the online UPS Provided that wherever the online UPS could not be installed due to the site not being ready or for any reason attributable solely to the Bank, the warranty shall terminate after 60 months for UPS from the date of Installation. The Supplier shall, in addition, comply with the performance guarantees specified under the Contract. If, for reasons attributable to the Supplier, these guarantees are not attained in whole or in part, the Supplier shall, make such changes, modifications, and/or additions to the Goods or any part thereof as may be necessary in order to attain the contractual guarantees specified in the Contract at its own cost and expense and to carry out further performance tests in accordance with TCC Clause 7.
7.	Page no.36 Annexure – D Rating	a)- 3 KVA UPSs b)-6 KVA UPSs(with IGBT 150amp – 200amp) c)- 10 KVA (with IGBT – Three in Single out – Isolation)	a)- 3 KVA UPSs (Single phase in Single phase out) b)-6 KVA UPSs (Single phase in Single phase out) c)- 10 KVA (Three phase in Single phase out)



8.	Page no.36 Annexure – D Point no.1 Technology	IGBT/ PWM, Dual Microprocessor Controlled Double Conversion with Active Power Factor Correction.	IGBT/ PWM, Dual Microprocessor Controlled Double Conversion with Active Power Factor Correction with copper winding
9.	Page no.36 Annexure – D Point no.5 Intermediate DC Voltage	(i)3 KVA range 72-96 VDC (ii)6 KVA range 192 -264 VDC (iii)10 KVA Min 192 -264 VDC	(i) 3 KVA range 72-96 VDC (ii) 6 KVA range 192-240 VDC (iii)10 KVA Min 192-240 VDC
10	Page no.37 Annexure – D Point no.12.b Isolation Transformer	Isolation Transformer should be at Input and Output.	(i) 3 KVA UPS: 1.5 times or minimum 4.5 KVA Isolation transformer should be at Input side. (ii) 6 KVA UPS: 1.5 times or minimum 7.5 KVA Isolation transformer should be at Input and Output side. (iii) 10 KVA UPS: 1.5 times or minimum 12.5 KVA Isolation transformer should be at Input and Output side.

Kindly quote the tender as per the changes made.

Kindly check our website www.aryavart-rrb.com regularly to get the latest updates regarding tender Notice.

Yours faithfully,


(Akhilesh Chandra Tripathi)
General Manager

